BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

ME OF THE WORK : Providing Drinking Water Facilities In Ward No.13 In ettyhalli Sub Division

	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
	2	3	4	5	6
	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinery soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications	cum	641.12	316.94	Rupees Three Hundred Sixteen And Paise Ninety Four Only
	Stone dust / Grit	Cum	141.60	1060.00	Rupees One Thousand Sixty Only
3	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 100mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.	Mtr	472.00	1061.06	Rupees One Thousand Sixty One And Paise Six Only
4	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	cum	74.24	2001.28	Rupees Two Thousand One And Paise Twenty Eight Only
5	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms^thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications.	cum	75.96	5505.64	Rupees Five Thousand Five Hundred Five And Paise Sixty Four Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Description Of Work	Unit	Qty	Rate To Be Quoted	
			In Figures (Rs)	In Words (Rs)
2	3	4	5	6
oviding and laying cement concrete using 20 mm d down size granite coarse aggregates and fine gregates of ready mixed concrete (RMC) for R.C.C rks laid in 15 cms thick layers and well compacted rating, curing, finishing with necessary cement rtar, with all lead and lifts etc., complete (exclusive cost of steel and fabrication charges.)	cum	75.96	5770.64	Rupees Five Thousand Seven Hundred Seventy And Paise Sixty Four Only
ophysical investigation of site for sinking borewell supplying drinking water to the habitation either ough the hand pump, MWS or P.W.S.S. by vertical trical sounding by adopting venner or lumbergers's method, including reconnaissance vey of geological formation, Geological investigation existing ground water in vicinity, its quality, ntity & acceptability of the users indicating the tion of site, recommended depth of casing pipe uired to seal the top unconsolidated formation uding an extra depth of 1.0 mtr in consolidated nation for proper seating of casing pipe, depth of ing required to cover full depth of aquifer posed to be tapped, probable yield and other rmation required including transportation of rument and accessories to work site, engaging nical personal and labour required etc150kg/cum coarse agggregate 0.86 cum, fine aggregate cum using concrete batch mix plant at 75cum/hr acity with fixed form pave	Each	1.00	2065.00	Rupees Two Thousand Sixty Five Only
cing of borewell of 165 mm dia clear using super hydraulic rig of capacity 250 PSIG & above 900 & above in all strata including over budern upto m. fixing of casing pipes, collars & cap with ssary cutting, threading & welding including sportation of rig and supporting vehicle, crew ges & cost of consumables etc., complete uding yield testing at the final depth with mum working of compressor for one (excluding cost of casing pipes, collars, cap using needle, screed and plate vibrator and ned in a continuous operation including provision contraction, expansion, construction and tudinal joints including groove cutting charges, filler, separation membrane, selant primer, joint nt, admixtures as approved, curing compound, ning to lines and grades as per drawing complete r specifications. - M30 (at 360Kg per cum coarse gate @ 0.69cum and fine aggregate @ 0.46cum) to 50.00 Mtr.	Mtr	50.00	315.80	Rupees Three Hundred Fifteen And Paise Eighty Only

UTIVE ENGINEER-4
L BBMP DIVISION
GALURU-560 010

Of The Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
	2	3	4	5	6
	50.00 to 100.00 Mtr.	Mtr	50.00	412.60	Rupees Four Hundred Twelve And Paise Sixty Only
	100.00 to 150.00 Mtr.	Mtr	50.00	458.35	Rupees Four Hundred Fifty Eight And Paise Thirty Five Only
	150.00 to 200.00 Mtr.	Mtr	50.00	484.10	Rupees Four Hundred Eighty Four And Paise Ten Only
	200.00 to 250.00 Mtr.	Mtr	50.00	560.32	Rupees Five Hundred Sixty And Paise Thirty Two Only
	250.00 to 300.00 Mtr.	Mtr	50.00	600.49	Rupees Six Hundred And Paise Forty Nine Only
	300.00 to 350.00 Mtr.	Mtr	50.00	622.00	Rupees Six Hundred Twenty Two Only
9	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/!993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes)	Rmt	42.00	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
10	Providing and fixing 250mm dia PVC pipe and as per specification and directions.	Rmt	6.00	1100.00	Rupees One Thousand One Hundred Only
11	175 mm dia M.S. Casing cap	Each	1.00	100.00	Rupees One Hundred Only
12	supply of 175mm M.S collars each	Each	7.00	150.00	Rupees One Hundred Fifty Only

EXECUTIVE ENGINEER-4
KRIDL, BDMT DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Description Of Work	Unit	Qty	Rate To Be Quoted	
			In Figures (Rs)	In Words (Rs)
2	3	4	5	6
13 Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 15HP/11KW 25 stage	Nos	1.00	63986.90	Rupees Sixty Three Thousand Nine Hundred Eighty Six And Paise Ninety Only
14 Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe	Rmtr	260.00	542.72	Rupees Five Hundred Forty Two And Paise Seventy Two Only
15 Coller	Each	27.00	212.00	Rupees Two Hundred Twelve Only
16 Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia	Rmt	285.00	164.29	Rupees One Hundred Sixty Four And Paise Twenty Nine Only
17 Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	Nos	1.00	14800.00	Rupees Fourteen Thousand Eight Hundred Only

EXECUTIVE ENGINEER R-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
	2	3	4	5	6
18	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm	Sqm Cm	22000.00	0.34	Rupees And Paise Thirty Four Only
19	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's	1.00	1800.00	Rupees One Thousand Eight Hundred Only
20	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve.	No's	2.00	1016.95	Rupees One Thousand Sixteen And Paise Ninety Five Only
21	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia	No's	4.00	1482.21	Rupees One Thousand Four Hundred Eighty Two And Paise Twenty One Only
22	Providing and fixing of 50mm GI Shortbend to motor	No's	2.00	232.14	Rupees Two Hundred Thirty Two And Paise Fourteen Only
23	Providing and fixing of 50mm GI union to the motor	No's	2.00	237.12	Rupees Two Hundred Thirty Seven And Paise Twelve Only
24	suppling & fixing of 50mm GI Elbow	No's	1.00	111.80	Rupees One Hundred Eleven And Paise Eighty Only
25	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m)	Per length	52.00	90.64	Rupees Ninety And Paise Sixty Four Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
	2	3	4	5	6
26	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type. (MR)	No's	1.00	475.00	Rupees Four Hundred Seventy Five Only
27	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP	No's	1.00	906.40	Rupees Nine Hundred Six And Paise Forty Only
28	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable	Mtr	35.00	169.95	Rupees One Hundred Sixty Nine And Paise Ninety Five Only
29	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces	Mtr	35.00	56.65	Rupees Fifty Six And Paise Sixty Five Only
30	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	3.00	249.26	Rupees Two Hundred Forty Nine And Paise Twenty Six Only
31	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia	No's	1.00	1699.50	Rupees One Thousand Six Hundred Ninety Nine And Paise Fifty Only
32	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,	No's	1.00	271.92	Rupees Two Hundred Seventy One And Paise Ninety Two Only
33	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. (MR)	No's	1.00	1350.00	Rupees One Thousand Three Hundred Fifty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
	2	3	4	5	6
34	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc,. Complete. 50mm dia	No's	2.00	778.04	Rupees Seven Hundred Seventy Eight And Paise Four Only
35	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	No's	1.00	311.58	Rupees Three Hundred Eleven And Paise Fifty Eight Only
36	Erection of pumping machineries PRE SR 12-13 pg 51/10.3.20	No	1.00	900.00	Rupees Nine Hundred Only
37	KPTCL Deposit charges	L/S	1.00	13300.00	Rupees Thirteen Thousand Three Hundred Only
38	Borewell registration charges per Rs 1000 each for BWSSB	L/S	1.00	1000.00	Rupees One Thousand Only
39	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete (external work) 40mm nominal OD pipes	Rmt	43.00	309.52	Rupees Three Hundred Nine And Paise Fifty Two Only
40	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete (external work) 25mm nominal OD pipes	Rmt	7.50	189.74	Rupees One Hundred Eighty Nine And Paise Seventy Four Only
41	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete (internal work exposed on wall) 20mm nominal OD pipes	Rmt	3.00	154.76	Rupees One Hundred Fifty Four And Paise Seventy Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
	2	3	4	5	6
42	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 40mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications	Each	3.00	1102.40	Rupees One Thousand One Hundred Two And Paise Forty Only
43	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications	No's	5.00	149.46	Rupees One Hundred Forty Nine And Paise Forty Six Only
44	Supplying of 40mm dia Elbows	No's	5.00	76.53	Rupees Seventy Six And Paise Fifty Three Only
45	Supplying of 25mm dia Elbows	No's	5.00	36.15	Rupees Thirty Six And Paise Fifteen Only
46	Supplying of 40mm dia Union	No's	5.00	156.67	Rupees One Hundred Fifty Six And Paise Sixty Seven Only
47	Supplying of 25mm dia Union	No's	5.00	82.57	Rupees Eighty Two And Paise Fifty Seven Only
48	Supplying of 25mm dia Nipple	No's	5.00	34.03	Rupees Thirty Four And Paise Three Only
49	Supplying of 25mm dia Reducer Elbow	No's	5.00	43.46	Rupees Forty Three And Paise Forty Six Only
50	Supplying of 25mm dia Reducer socket	No's	5.00	29.83	Rupees Twenty Nine And Paise Eighty Three Only
51	Supplying of 40mm dia Tees	No's	5.00	106.32	Rupees One Hundred Six And Paise Thirty Two Only
52	Filling available earth around pipe lines cable in layers not exceeding 20cms, in depth compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost all labour complete as per specifications	Cum	544.95	213.06	Rupees Two Hundred Thirteen And Paise Six Only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner